



QUESTIONS & RESPONSES #01

BID / TITLE 070941 | EBC Bldg 326 HVAC & Roof Replacement & Bldgs 407 & 532 Bird Wire

CONTACT Heather Shadko, PROCUREMENT

EMAIL procurement@portoftacoma.com

PHONE NUMBER 253-428-8697

SUBMITTAL DUE DATE February 5, 2019 @3:00PM (PST)

Q&A ISSUE DATE January 28, 2019

PROPOSER QUESTIONS	PORT RESPONSES	RFP/ RFQ Section
Do you have any further information on this? What type of HVAC system are looking to use? Are you looking to get new DDC system as well?	Reference M-series drawings and divisions 20, 22, 23 specifications for requirements.	
New panel schedule shown on E5.01 includes remarks about GFCI breakers shown with an asterisk*. There are no asterisks shown at individual breaker locations. Can you verify that no GFCI breakers are needed?	There are no GFCI breakers required unless you prefer to install for GFCI protection of roof top receptacles in lieu of GFCI wiring devices.	
Drawing E1.01 note 4 states to demo wiring back to source. Drawing E2.01 note 5 states to provide new wiring secured to molded pyramid block supports. This note makes it seem as if we will also be replacing the conduit. Can you clarify if we are removing wiring as well as the conduit pathway and then installing new wiring and conduit pathway secured to blocks?	Wiring is considered to be conductors installed in an approved raceway system. Wires are considered to be conductors. See addendum 1 for additional definitions.	
Drawing E2.01 note 1 states that the new mechanical equipment RTU3, RTU4 and RTU5 is furnished with an integral GFCI, but RTU3 shows a new GFCI per note 4. Please verify that we are providing a total of (3) GFCIs, one at each of RTU1, RTU2, and RTU3.	Delete plan note 1 at RTU 3. See addendum 1.	

Drawing E2.01 note 1 states that the new mechanical equipment RTU3, RTU4 and RTU5 is furnished with an integral Disconnect, but RTU3 shows a new disconnect that division 26 should furnish and install per the mechanical schedule. Please verify whether or not Division 26 is to furnish and install a new disconnect at RTU3.	Delete plan note 1 at RTU 3. See addendum 1.	